

PROPOSED WORKS ESTIMATE

Next-Stage Renovation and Finishing Works

Budget estimate for the next phase of converting the existing back apartment into a completed two-bedroom flat at Ipoti, Ekiti State.

PREPARED FOR

Ayeni Franlin
Client

PROJECT

Back-apartment renovation
Conversion to a two-bedroom flat

ESTIMATE REFERENCE

NBC-EST/2026/IPT-001

PREPARED BY

Nature's Beauty Construction
A division of Jenyo Akarakiri Global Enterprise

SITE

Ipoti, Ekiti State

DATE OF ISSUE

6 September 2026

TOTAL PROPOSED WORKS ESTIMATE

₦8,650,500

Eight million, six hundred and fifty thousand, five hundred naira only.

Scope at a Glance

PROPOSED WORK CATEGORY	AMOUNT (₦)
Casement windows	1,120,000
Doors and installation of doors/windows	2,100,000
Floor and wall tiling, materials and labour	2,430,500
Internal screeding	350,000
Painting works	800,000
Electrical installation, materials and labour	600,000
Plumbing and sanitary works	650,000
Two bedroom wardrobes	600,000
Total proposed works	8,650,500

Estimate basis. This document covers the proposed next-stage works only. The previously completed roof, masonry, plastering and POP-ceiling works are recorded separately and are not included in this total.

Detailed Cost Schedule

A · Casement Windows

DESCRIPTION	QUANTITY	RATE (₦)	AMOUNT (₦)
Type A casement windows — 3 ft × 4 ft	6 no.	160,000	960,000
Type B toilet casement windows — 2 ft × 2 ft	2 no.	80,000	160,000
Casement windows subtotal			1,120,000

B · Doors and Installation

DESCRIPTION	QUANTITY	RATE (₦)	AMOUNT (₦)
Strong wooden internal doors — 3 ft wide	4 no.	350,000	1,400,000
Turkish security entrance door	1 no.	550,000	550,000
Installation of all doors and windows	Lump sum	—	150,000
Doors and installation subtotal			2,100,000

C · Floor and Wall Tiling

DESCRIPTION	QUANTITY	RATE (₦)	AMOUNT (₦)
Floor tiles	70 m ²	8,200/m ²	574,000
Wall tiles	85 m ²	6,600/m ²	561,000
Sharp sand	2 trips	80,000	160,000
Cement	50 bags	12,500	625,000
Gum cement / tile adhesive	10 bags	6,000	60,000
Tile trim profiles	15 lengths	3,200	48,000
J.O.Y. Portland white cement	1 bag	15,000	15,000
Tiling workmanship	155 m ²	2,500/m ²	387,500
Tiling subtotal			2,430,500

Measurement allowance. Tile quantities comprise 70 m² of floor tiles and 85 m² of wall tiles. The labour calculation is based on the combined 155 m² installation area.

Detailed Cost Schedule — Continued

SECTION	DESCRIPTION AND INCLUDED SCOPE	AMOUNT (₦)
D	Internal screeding. Internal wall preparation and screeding, including screeding materials, white cement and labour.	350,000
E	Painting works. Ceiling emulsion, satin finish to internal walls, matt finish to external walls, surface preparation and painting labour.	800,000
F	Electrical installation. Conduit piping, 1.5 mm ² , 2.5 mm ² and 4 mm ² wiring, accessories, socket outlets, AC points, small distribution board with protective breakers, LED lighting, sitting-room chandelier, installation, testing and labour.	600,000
G	Plumbing and sanitary works. Two WC sets, new pipe runs, plumbing and piping accessories, installation, testing, labour and incidental allowance.	650,000
H	Bedroom wardrobes. One wardrobe in each of the two bedrooms.	600,000

Consolidated Estimate

REF.	WORK CATEGORY	AMOUNT (₦)
A	Casement windows	1,120,000
B	Doors and installation of doors/windows	2,100,000
C	Floor and wall tiling, materials and labour	2,430,500
D	Internal screeding	350,000
E	Painting works	800,000
F	Electrical installation, materials and labour	600,000
G	Plumbing and sanitary works	650,000
H	Two bedroom wardrobes	600,000

Total Proposed Works Estimate

8,650,500

COMMERCIAL BASIS

Rates are budget estimates and remain subject to final supplier confirmation, product selection and site verification. VAT has not been added.

SCOPE CONTROL

Any work, quantity or specification outside this schedule will be treated as a variation and agreed before execution.

MATERIALS

Final colours, finishes, brands and models are subject to the client's approval and prevailing market availability.

PAYMENT

Mobilisation and stage-payment arrangements are to be agreed before procurement and commencement of the proposed works.

For Nature's Beauty Construction

Name · Signature · Date

Client acceptance

Ayeni Franlin · Signature · Date