

QUOTATION

Itemised Proposed Renovation Works Estimate

CLIENT	LOCATION
Ayeni Franlin	Ipoti, Ekiti State
PROJECT	DATE
Renovation of the back apartment into a two-bedroom flat	6 September 2026

Detailed Cost Breakdown

A. Casement Windows

REF.	DESCRIPTION	QTY.	RATE (₦)	AMOUNT (₦)
A1	Type A casement window — 3 ft × 4 ft	6 no.	160,000	960,000
A2	Type B toilet casement window — 2 ft × 2 ft	2 no.	80,000	160,000
Casement windows subtotal				1,120,000

B. Doors and Installation

REF.	DESCRIPTION	QTY.	RATE (₦)	AMOUNT (₦)
B1	Strong wooden internal door — 3 ft wide	4 no.	350,000	1,400,000
B2	Turkish security entrance door	1 no.	550,000	550,000
B3	Installation of all doors and windows	Lump sum	—	150,000
Doors and installation subtotal				2,100,000

C. Floor and Wall Tiling

REF.	DESCRIPTION	QTY.	RATE (₦)	AMOUNT (₦)
C1	Floor tiles	70 m²	8,200/m²	574,000
C2	Wall tiles	85 m²	6,600/m²	561,000
C3	Sharp sand	2 trips	80,000	160,000
C4	Cement for tiling, door installation and other works requiring cement	35 bags	12,500	437,500
C5	Gum cement / tile adhesive	10 bags	6,000	60,000
C6	Tile trim profiles	15 lengths	3,200	48,000
C7	J.O.Y. Portland white cement	1 bag	15,000	15,000
C8	Tiling workmanship	155 m²	2,500/m²	387,500
Floor and wall tiling subtotal				2,243,000

Detailed Cost Breakdown — Continued

D. Internal Wall Screeding

REF.	DESCRIPTION	QTY.	AMOUNT (₹)
D1	Internal wall preparation and screeding, including materials, white cement and labour	Lump sum	350,000
Internal screeding subtotal			350,000

E. Painting Works

Itemised from the painter’s Ipoti estimate supplied by the client.

REF.	DESCRIPTION	QTY.	RATE (₹)	AMOUNT (₹)
E1	White emulsion paint	4 drums	27,000	108,000
E2	Satin paint for three rooms	2 drums	80,000	160,000
E3	Matt paint for external walls	4 drums	80,000	320,000
E4	Gloss paint for burglary protectors	1 gallon	20,000	20,000
E5	Gloss paint for kitchen wooden door	½ gallon	10,000	10,000
E6	Sandpaper	Allowance	—	6,000
E7	Filler	3 packets	500	1,500
E8	Petrol	Allowance	—	4,000
Painting materials subtotal				629,500
E9	Transportation	Lump sum	—	60,000
E10	Painting workmanship	Lump sum	—	190,000
Painting works subtotal				879,500

F. Electrical Installation

REF.	DESCRIPTION	QTY.	RATE (₹)	AMOUNT (₹)
F1	20 mm PVC conduit pipes	2 bundles	15,000	30,000
F2	1.5 mm² single-core copper cable	3 coils	31,000	93,000
F3	2.5 mm² single-core copper cable	1 coil	51,000	51,000
F4	4 mm² single-core copper cable	1 coil	83,000	83,000
F5	Electrical installation labour, conduit wiring, fittings, connections, transportation and incidental materials	Lump sum	—	170,000
F6	13A double socket outlets	6 no.	7,500	45,000
F7	20A AC control switches / AC points	3 no.	5,000	15,000
F8	Small distribution board with protective breakers	1 no.	60,000	60,000
F9	Standard small LED ceiling/downlights	8 no.	3,900	31,200
F10	Chandelier for sitting room	1 no.	50,000	50,000
Electrical installation subtotal				628,200

Detailed Cost Breakdown — Continued

G. Plumbing and Sanitary Works

REF.	DESCRIPTION	QTY.	RATE (₦)	AMOUNT (₦)
G1	WC sanitary sets	2 sets	120,000	240,000
G2	New pipe runs and plumbing accessories	Allowance	—	150,000
G3	Plumbing installation labour and testing	Lump sum	—	100,000
G4	Allowance for sanitary fittings, toilet fittings, connections, taps, valves and incidental materials	Provisional	—	160,000
Plumbing and sanitary works subtotal				650,000

H. Bedroom Wardrobes

REF.	DESCRIPTION	QTY.	RATE (₦)	AMOUNT (₦)
H1	Bedroom wardrobe — one in each bedroom	2 no.	300,000	600,000
Bedroom wardrobes subtotal				600,000

Consolidated Estimate

REF.	WORK CATEGORY	AMOUNT (₦)
A	Casement windows	1,120,000
B	Doors and installation	2,100,000
C	Floor and wall tiling	2,243,000
D	Internal wall screeding	350,000
E	Painting works	879,500
F	Electrical installation	628,200
G	Plumbing and sanitary works	650,000
H	Bedroom wardrobes	600,000
Total Estimated Cost		8,570,700

Amount in words: Eight million, five hundred and seventy thousand, seven hundred naira only.

Pricing note: Prices are estimates and may be adjusted following final material selection, supplier confirmation, site verification or changes to the scope of work. VAT has not been added.

Nature’s Beauty Construction
Name · Signature · Date

Client acceptance
Ayeni Franlin · Signature · Date