

SEPARATE QUOTATION

Soakaway / Septic Tank Construction Estimate

CLIENT Ayeni Franlin	LOCATION Ipoti, Ekiti State
INTERNAL DIMENSIONS 3.0 m × 2.4 m × 2.4 m deep	DATE 6 September 2026

Construction Basis

225 mm blockwork; internal wall plastering; four assumed corner columns; 150 mm concrete cover slab with a 300 mm overhang on all sides; and 12 mm reinforcement at 150 mm centres in both directions.

REF.	DESCRIPTION	QTY.	RATE (₦)	AMOUNT (₦)
1	Excavation	Lump sum	—	100,000
2	225 mm sandcrete blocks	400 no.	800	320,000
3	Cement for blockwork, internal plastering, columns and cover slab	35 bags	12,500	437,500
4	Sharp sand for blockwork, plastering and concrete	1 trip	80,000	80,000
5	Granite for columns and cover slab	From site stock	—	—
6	12 mm × 12 m reinforcement bars	23 lengths	14,000	322,000
7	Binding wire	1 roll	10,000	10,000
8	Labour for laying blocks	400 blocks	150/block	60,000
9	Iron-bending labour	Lump sum	—	30,000
10	Carpentry and formwork labour	Lump sum	—	50,000
11	Concrete-casting labour	Lump sum	—	50,000
12	Internal wall plastering labour	Lump sum	—	15,000
Current Estimated Cost				1,474,500

Amount in words: One million, four hundred and seventy-four thousand, five hundred naira only.

Important: Granite is to be taken from existing site stock and therefore carries no new purchase cost in this estimate.

Reinforcement calculation: 18 lengths for a single-layer cover-slab mat and 5 lengths for four assumed corner columns. Final reinforcement and structural details should be confirmed before construction.

Nature’s Beauty Construction
Name · Signature · Date

Client acceptance
Ayeni Franlin · Signature · Date